ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Dated 26th January 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 14th February 1927, for Restoring the Vadigenahalli Tank R. No. 22, Hoskote Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees three hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring the Vadigenahalli Tank R. No. 22 of Hoskote Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

RESTORING VADIGENAHALLI TANK REGISTER NO. 22 OF HOSKOTE TALUK.

No.	Items of work	Per	Quantity
	Bund.		
1	Jungle clearing	Grade	23
2	Earthwork cutting grips, etc.	C.yd.	1120
3	Earthwork to bund with watering and tamping	,,	14·586
4	Removing sand and silt	,,	1706
5	New stone work	,,	1054
6	Old stone work with new jelly	,,	100
7	Turfing	S.ft.	6300
8	Providing new grade stones with painting and numbering	No.	12
9	Refixing old grade stones	,,	11
10	Index stones	,,	23
11	B. M. stones	,,	2
12	Registered No. stones	,,	1
13	Gauge stone	,,	1
	Sluice.		
1	Repairing the existing sluice including plug and iron rod and locking arrangement.	Lump sum	
	Waste Weir at Right 200'.		
1	Earthwork excavation	C.yd.	319
2	Burnt brick in surki mortar	C.ft.	1447
3	Burnt stone slabs dressed 6" thick	S.ft.	327
4	Plastering with surki mortar	S.qr.	17·00
5	New stone work	C.yd.	100

R. W. SCALDWELL,
Executive Engineer.

UPPER CHANNELS DIVISION, YEDATORE.

Dated 22nd January 1927.

Notice is hereby given that sealed tenders will be received in the Office of the Executive Engineer, Upper Channels Division, up to 2 P.M., on the 12th February 1927, for the following works connected with the construction of Yedatore New Town. Approximate estimates of quantities are given below. These quantities are not guaranteed. The work should be completed by the end of the periods noted against each of the works.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Yedatore, between the hours of 11 A.M. and 5 P.M., on all office working days.

3. Separate tenders should be submitted for each of the works on printed forms which may be obtained from the Executive Engineer. A contractor may tender for any or all works. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Serial No.	Description of work.	Unit of work	Rate per unit

The description of items of work should be exactly in terms of the provision in the estimates given below.

4. Each tender must be accompanied by a deposit of the amount noted against each of the works in Cash or Government Promissory Notes as earnest money and be superscribed as tender for such a work, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Upper Channels Division, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor in each case, will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The names of the successful competitors whose tenders have been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned. The contractor must be prepared to execute any work or works for which the tenders are accepted even though some of his tenders are not accepted.

9. As the following old materials (will be available from the existing buildings that will be dismantled in the old Yedatore Town, the contractor in each case should bind himself to utilise the materials so supplied departmentally. The contractor will be given rates either for fixing only or the cost of the materials will be deducted from the rates for the whole item as found convenient by the Executive Engineer. Hence the following items may also be quoted for separately. In fixing rates for items where old materials will be utilised the Executive Engineer's decesion is final and must be accepted by the contractor.

Fixing.—

1. Teakwood work supplied by Government.
2. Honnewood do do
3. Doors do do
4. Windows do do
5. Ventilators do do
6. Burnt stone slabs for cills, lintals, steps and retaining walls.

Rates at which the Contractor agrees to accept deduction towards the cost of materials supplied by Government at site of Yedatore New Town out of the amount at the rates quoted for by the contractor may be noted in the case of:—

1. Mangalore tiles (flooring) 9″×9″ (Basel Mission.)
2. Mangalore Roofing tiles, (Basel Mission).
3. Eave boards 6″ and 9″ (ordinary)
4. Burnt stone slabs 3″, 4″ and 6″.
5. Honne wood reapers, 2″×1″.
6. Teakwood reapers, 2″×1″.
7. Cuddapah slabs, $1\frac{1}{4}$″ to $1\frac{1}{2}$″.

E B.

DETAILS OF WORK.

Serial No.	Name of work	Probable date of completion	Earnest money to be deposited
			Rs.
1	Constructing Taluk Cutcherry	To be completed up to top of basement by 10th June 1927, and in every respect during 1927-28 in the period fixed by the Executive Engineer.	500
2	Do witness shed	10th May 1927...	25
3	Do Combined Dispensary and In-patient Ward.	10th June1927 ...	250
4	Do Sub-Assistant Surgeon's Quarters	Do	125
5	Do Midwife's Quarters ...	May 1927	50
6	Do Third Class Travellers' Bungalow.	10th June 1927...	250
7	Do Reading Room	May 1927 ...	100

TALUK CUTCHERRY.

No.	Items of work	Unit	Quantity
1	Earthwork excavation	C.yds.	436
2	Concrete in mortar	C.ft.	6,686
3	Trap stone in mortar	"	7,688
4	Burnt brick in mud in superstructure	"	11,061
5	Burnt brick in chunam	"	3,609
6	Arch work brick in chunam	"	89
7	Plastering in chunam	Sqrs.	286·90
8	White and colour washing	"	286·90
9	Honney wood work wrought and put up with wood oiling	C.ft.	694·94
10	Roofing with first Class Mangalore tiles (Basel Mission) on teak reapers.	Sqr.	82·37
11	Ridge tiles set in mortar	R.ft.	456
12	Chunam borders over roof	"	266
13	Terracing with brick on edge on 3" concrete and 3 layers of flat tiles and plastering, etc., complete.	Sqr.	12·31
14	Brick in chunam parapet ordinary	R.ft.	158
15	Ornamental lovey work in front above windows each ...	No.	36
16	Cuddapah slabs above brackets	Sqrs.	401
17	Beading below brackets	R.ft.	74
18	Brick work for sloping with plastering	C.ft	139
19	Parapet wall ordinary	R.ft.	36
20	Constructing pilasters 4½" thick with architrave, etc., in front of door opening.	Each	4
21	Ornamental cornice for the bases of pillars ...	"	2
22	Burnt stone slabs dressed and fixed 6" thick ...	S.ft.	1,873
23	Teakwood pillars with base and capital	Each	22
24	Flooring with Cuddapah slabs on 3" concrete bed and cement pointing.	Sqrs.	67·29
25	Teakwood doors pannelled 1½" thick shutter with iron clamps and fittings, etc., complete.	S.ft.	685

No.	Items of work	Unit	Quantity
26	Teakwood lock-up doors as per new type design with iron clamps and fittings, complete.	S.ft.	98
27	Teakwood doors for treasury with iron bars and fittings with stone post.	Lump sum.	
28	Teakwood pannelled windows with double wooden shutters inside glazed shutters with clamps ¾" iron bars and glazed ventilators, on top.	S.ft.	1,365
29	Teakwood ventilators with iron bars ¾" with perforated wire netting, etc., complete.	"	109
30	Teakwood circular ventilators with glazed shutters, complete.	No.	14
31	Teakwood finials	"	6
32	Do terminals	"	18
33	Ornamental cast iron gate as per design including fixing, etc., complete.	Each	1
34	Iron gratings including fixing, etc., complete ...	No.	6
35	Pointing with mortar with cement wash to basement ...	Sqrs.	18·77
36	Chocolate painting two coats	"	58·18
37	Ornamental barge board	No.	4
38	Gravel collection and consolidation to Courtyard ..	Sq.yds.	821
39	Teakwood planks ½" thick with Zinc sheet 3' width for vallyes including fixing.	S.ft.	153
40	Ornamental wooden railing with bottom and top bars including door and iron fittings, complete.	R.ft.	27
41	Providing teakwood Dias for the Amildar's Court Hall with railings steps, etc., complete.	Lump sum.	
42	Providing witness box	Lump sum.	
43	Surki concrete U-shaped drain with plastering, etc., complete.	R.ft.	333
44	Lead off box drain with plastering	"	50
45	Providing date stone	No.	1
46	Constructing latrine	Lump sum.	
47	Clearing site and opening out roads	Lump sum.	
48	Providing small cistern for lock-up rooms	Lump sum.	
49	Providing wooden racks for record rooms	Lump sum.	
50	Planting Avenue Trees	Lump sum.	
51	Constructing a kitchen for prisoners	Lump sum.	
52	Water connection	Lump sum.	

WITNESS SHED.

1	Earthwork excavating foundation and filling in basement	C.yds.	3
2	Burnt brick in mud	C.ft.	265
3	Burnt stone slabs 6" thick dressed and fixed ...	S.ft.	78
4	Teakwood work wrought and put up	C.ft.	13·50
5	Plastering with chunam	Sqrs.	4·38
6	Whitewashing two coats	"	4·38
7	Cutting grooves in pillers	Nos.	8
8	Teakwood wicket gates with hinges, bolts, etc., complete including painting.	S.ft.	12
9	Teakwood eave-board ordinary	R.ft.	36
10	Flooring 3" concrete including plastering with chunam ...	Sqrs.	1·55
11	Roofing with First Class Mangalore tiles on teak reapers, complete.	"	3·24
12	Ridge tiles set in mortar	R.ft.	18
13	Mortar bands over roof	"	36

COMBINED DISPENSARY AND IN-PATIENT WARD.

No.	Items of work	Unit	Quantity
1	Earth work excavation	C.yds.	88
2	Concrete in mortar in foundation	C.ft.	791
3	Brick in mortar	,,	2,147
4	Brick in mud	,,	3,293
5	Burnt stone slabs 6" thick dressed and fixed... ...	S.ft.	538
6	Flooring with Cuddapah slabs on 3" concrete bed with cement pointing.	Sqrs.	3·40
7	Do do square tiles (Basel Mission)	,,	9·28
8	Doors teakwood with panelled shutters and glazed ventilators at top.	S.ft.	281
9	Teekwood circular ventilators with glazed shutters ...	,,	38
10	Teakwood windows with panelled shutters and glazed ventilators at top ½" iron bars and glazed shutters inside.	,,	329
11	Rectangular ventilators with glazed shutters ...	,,	12
12	Teakwood wall-shelf with shutter	,,	94
13	Teakwood work wrought and put up with wood-oiling ...	C.ft.	104·17
14	Plastering with mortar	Sqrs.	72·51
15	White and colour washing two coats	,,	72·51
16	Burnt stone pillars with base and capital	No.	6
17	Roofing with First Class Mangalore tiles on teak reepers	Sqrs.	23·75
18	Ridge tile set in morts	R.ft.	115
19	Ornamental eave-board	,,	273
20	Teakwood finials large	No.	3
21	Do small	,,	1
22	Teakwood terminals large	,,	10
23	Do small	,,	2
24	Moulding alround windows	Each	2
25	Cut boards with brackets	R.ft.	24
26	Painting with silicate	Sqrs.	13·08
27	Providing zinc sheets and plank ½' for valley with cement plastering.	,,	58
28	Constructing cisterns	No.	2
29	Clearing site and levelling ground	Lump sum.	
30	Tarring wood work	Lump sum.	
31	Brick in mud *(for kitchen)*	C.ft.	486
32	Honney wood work	,,	8·95
33	Teakwood door and shutters	S.ft.	18
34	Do windows with iron bars	,,	12
35	Flooring with concrete and plastering	Sqrs.	0·70
36	Earth work excavation	C.yd.	4
37	Plastering with mortar	Sqrs.	4·37
38	Roofing with First Class Mangalore tiles on teak reepers	,,	2·21
39	Ridging with Mangalore tiles	R.ft.	18
	Latrine.		
40	Earthwork excavation	C.yds.	5
41	Plastering with mortar	Sqrs.	3·63
42	Brick in mud	C.ft.	303
43	Coping with brick in mortar and plastering	R.ft.	33
	Dead House.		
44	Earthwork excavation	C.yds.	17
45	Burnt stone slabs 6" thick	S.ft.	41
46	Flooring with Cuddapah slabs on 3" concrete ...	Sqrs.	1·50
47	Teakwood wrought and put up with woodoiling ...	C.ft.	15

No.	Items of work	Unit	Quantity
48	Plastering with mortar	Sqr.	5·79
49	Roofing with 1st class Mangalore tiles on teak reapers ...	,,	3·57
50	Ridging with Mangalore tiles	R.ft.	17
51	Burnt brick in mud	C.ft.	3·33
52	Burnt stone in mortar	,,	4·92
53	Honey comb with country tiles	Sqr.	2·05
54	Whitewashing	,,	5·79
55	Teakwood battened door	S.ft.	18
56	Chocolate painting	Sqr.	1·04
57	Burnt stone slabs sloping towards the centre nicely dressed and polished.	S.ft.	20
58	Teakwood windows battened with iron bars and glazed shutters.	,,	10
59	Do gauze wire netting battened shutter ..	,,	24
60	Wrought iron pipe for drainage	R.ft.	12

SUB-ASSISTANT SURGEON'S QUARTERS AT YEDATORE NEW TOWN.

1	Earth excavation foundation	C.yd.	70
2	Filling foundation with concrete	C.ft.	578
3	Burnt brick in mud for foundations and basement ...	,,	1641
4	Burnt brick in chunam for coping	R.ft.	42
5	Burnt brick in mud for superstructure	..	2015
6	Burnt stone slabs dressed and fixed	S.ft.	297
7	Teakwood battened doors with iron fitting, etc., complete.	,,	194
8	Honney wood work wrought and put up with wood oiling, etc., complete.	C.ft.	66·60
9	Roofing with 1st class Mangalore tiles on teak reapers, etc., complete.	Sqr.	13·48
10	Teakwood pillers with base and capitals, etc., complete...	Each	6
11	Ridge tiles in mortar	R.ft.	62
12	Teakwood eave boards, ordinary	,,	157
13	Constructing U-shaped and lead off drains	...	Lumpsum
14	Teakwood panelled windows with glazed shutters 2/16" iron bars, etc., complete.	S.ft.	61
15	Teak battened shutters for windows with iron bars and other iron fittings, etc., complete.	,,	42
16	Zinc sheet for the vellays includingteak wood planks underneath.	R.ft.	96
17	Plastering with chunam	Sqr.	44·45
18	White and colour wash	,,	44·45
19	Flooring with Mangalore tiles on 3" concrete and cement pointing, etc., complete.	,,	2·30
20	Gravelling the compound	...	Lumpsum
21	Flooring with Cuddapah slabs on 3" concrete bed and cement pointing, etc., complete.	Sqr.	4·79
22	Chocolate painting two coats	,,	5·94
23	Wood oiling	,,	2·55
24	Constructing combined chimney	...	Lumpsum
25	Constructing seats in latrine, stove flagging ...	...	do
26	Providing mortar and pestle	...	do
27	Do iron clamps to doors and windows ..	Each	96
28	Cupboards with pegs to support	...	Lumpsum

MIDWIFE'S QUARTERS.

No.	Items of works	Unit	Quantity
1	Earthwork excavation and filling the same to basement	C.yds.	16
2	Stone in mud	,,	704
3	Burnt brick in mud	,,	1091
4	Plastering with chunam mortar	Sqr.	18·47
5	Whitewashing	,,	1935
6	Teakwood wrought and put up	C.ft.	45·95
7	Teakwood battened doors with iron fittings, etc., complete.	S.ft.	101
8	Teakwood windows with ½" iron bars and single battened shutters fitting, etc., complete.	,,	51
9	Burnt stone slabs	,,	94
10	Cutting grooves in stone pillars of front verandah (for seat of Bressumer).	No.	3
11	Coping with burnt brick in mud and chunam plastering...	R.ft.	50
12	Roofing with 1st class Mangalore tiles on teakwood reapers.	Sqr.	7·05
13	Do ridge tiles	R.ft.	24
14	Chunam plastering over 3" concrete to flooring ...	Sqr.	3·60
15	Cornice 9" thick with burnt brick in chunam plastering, etc., complete.	R.ft.	24
16	Binding wall over roof	,,	60
17	Lead off drains to latrine	...	Lumpsum
18	Painting doors and windows	Sqrs.	4·56

Constructing a 3rd Class Travellers' Bungalow with Kitchens and Motor Shed.

No.	Items of works	Unit	Quantity				Total
			Main	Indian kitchen	European kitchen	Motor shed	
1	Earthwork excavation	C.yd.	50	14	17	7	88
2	Size stone in mud foundation and basement	C.ft.	1,347	385	445	189	2,366
3	Burnt brick in mud	,,	3,402	1,033	889	538	5,862
4	Arch work brick in mortar	,,	21	..	24	..	45
5	Burnt stone slabs dressed and fixed ...	S.ft.	336	100	45	18	499
6	Teakwood pillars with base and capital ...	No.	6	..	..	..	6
7	Teakwood wrought and put up ...	C.ft.	128·65	25·90	35·08	24·85	214·48
8	Teakwood doors panalled with iron fittings.	S.ft.	155	..	..	..	155
9	Teakwood double doors with panelled shutters and iron fittings.	,,	25	..	..	..	25
10	Teakwood battened doors with iron fittings	,,	..	90	14	..	104
11	Teakwood windows with ½" iron bars with inside glazed shutters and outside panelled shutters, complete.	,,	54	24	..	..	78
12	Do battened shutters ...	..	..	..	..	5	5
13	Teakwood circular ventilators with glazed shutters.	,,	4	..	..	..	4
14	Teakwood rectangular ventilators with glazed shutters inside and battened shutters outside	,,	..	4	..	..	4
15	Roofing with 1st class Mangalore tiles (Basel Mission) on teak reapers.	Sqr.	19·30	6·33	7·31	3·93	36·87
16	Ridge tiles set in mortar ...	R.ft.	107	27	40	20	194
17	Plastering with chunam ...	Sqr.	38·69	21·93	20·40	9·14	90·16
18	Flooring with Cuddapah slabs on 3" concrete bed and cement pointing.	,,	5·03	1·22	...	...	6·25
19	Flooring with Mangalore tiles (Basel Mission) on 3" concrete bed and cement pointing.	,,	5·04	1·50	..	..	6·54
20	Flooring with 6" concrete including plastering.	...	...	...	1·20	..	1·20
21	Flooring with gravel 6" thick ...	,,	..	..	2·00	..	2·00
22	Painting to doors and windows two coats ...	,,	6·15	3·37	..	..	9·52
23	White and color washing two coats ...	,,	38·69	21·93	20·40	9·14	90·16
24	Teakwood eave board 9" x 1" ornamental ...	R.ft.	169	53	..	..	222
25	Binding walls over roofs	,,	88	60	64	36	248
26	Constructiong dwarf wall for bath cistern including cement plastering.	,,	18	..	..	..	18
27	Constructing cisterns	...	...	L. S.	..	...	...
28	Constructing a platform and oven with brick in mud with arch ways.	C.ft.	..	..	108	..	108
29	Constructing a motor pit ...	...	..	..	..	L. S.	...
30	Vertical slabs including rounding at top and cutting grooves for inserting bamboos.	S.ft.	..	..	..	16	16
31	Providing grinding stone	...	...	L. S.	..	..	—
32	Constructing cistern and ovens	...	..	,,			
33	Clearing site and levelling ground ...	...	...	,,	,,	L. S.	...

READING ROOM AT YEDATORE NEW TOWN.

No.	Items of work	Unit	Quantity
1	Earthwork excavating foundation and filling the same to basement level.	C.yds.	22
2	Concrete in chunam	C.ft.	154
3	Stone in chunam	,,	647
4	Burnt brick in mud	,,	1260
5	Burnt stone slabs 6" thick roughly dressed	S.ft.	155
6	Plastering with chunam	Sqr.	27·14
7	White and clour washing	,,	27·14
8	Teakwood work wrought and put up with wood oiling ...	C.ft.	67·09
9	Zinc sheets for valley	S.ft.	32
10	Roofing with 1st class Mangalore tiles over teakwood reapers 1" thick, etc., complete.	Sqr.	11·92
11	Teakwood pillars 6¼' x 4" x 4" with capital	No.	4
12	Ridge tiles set in mortar	R.ft.	45
13	Teakwood ornamental eave board	,,	143
14	Flooring with Cuddapah slabs over 3" concrete bed with cement pointing.	Sqr.	6·44
15	Teakwood battened doors with iron fittings and iron clamps, etc., complete	S.ft.	39
16	Teakwood windows with battened shutters and ¾" iron bars.	,,	61
17	Chocolate painting to doors and windows	Sqr.	2·00
18	Binding wall (9" x 9")	R.ft.	44
19	Chunam borders	,,	36
20	Clearing site and levelling ground	Lumpsum	...
21	Teakwood finial	No.	1
22	Teak pendents	,,	4

No. 79, dated 24th January 1927.

Attention is invited to the notification dated 6th January 1927, published in the *Mysore Gazette* of the 20th January 1927, part VI, Pages 65 to 68 calling for the tenders for the different works connected with the Water-supply to Yedatore New Town. It may also be noted that the period fixed for the receipt of the tenders up to 2 P.M. of the 26th January 1927 has been extended up to 2 P.M. of the 7th February 1927.

N. SUBBA RAO,
Executive Engineer.

MEDICAL DEPARTMENT.

EPIDEMIC DISEASES HOSPITAL, MYSORE.

TENDER NOTICE.

Dated 22nd January 1927.

The attention of the public is invited to the detailed notification dated 25th December 1926, calling for tenders for the supply of bedding and clothing required for the use of the Epidemic Diseases Hospital, Mysore, for the calendar year 1927, published on pages 70 and 71, Part VI of the *Mysore Gazette* dated 20th January 1927.

B. KRISHNAMURTHY RAO,
Medical Officer.

MISCELLANEOUS DEPARTMENTS.

MYSORE HORTICULTURAL SOCIETY.

Dated 22nd January 1927.

The Winter Horticultural Show will be held at Lal-Bagh on Saturday and Sunday the 5th and 6th February 1927. It will be open on Saturday at 3 P.M. for members of the Horticultural Society and at 4 P.M. for the public.

On Sunday it will be open from 8A.M. to 8 P.M.